

FOUNDATION PLAN
1/4" = 1'-0"



FOUNDATION PLAN NOTES:

1. ALL ELEVATIONS ARE REFERENCED TO THE FINISHED GROUND FLOOR ELEVATION (0'-0"). SEE CIVIL DRAWINGS FOR ACTUAL ELEVATIONS. ELEVATIONS ARE DENOTED THUS (X'-X") ON PLAN.
2. (X) INDICATES COLUMN/WALL FOOTING TYPE. SEE FOOTING SCHEDULE ON THIS SHEET FOR ADDITIONAL INFORMATION.
3. TOP OF EXTERIOR FOOTING ELEVATIONS SHALL BE (-2'-0"), INTERIOR FOOTING ELEVATION SHALL BE (-2'-0") BELOW FINISHED FLOOR ELEVATION UNLESS OTHERWISE NOTED ON PLAN, THUS (-X'-X").
4. - - - - - INDICATES FLOOR CONSTRUCTION JOINT (C.J.) OR SAW JOINT (S.J.). SEE TYPICAL SLAB-ON-GRADE DETAILS ON SHEET S002. THE JOINTS SHOWN ON THE FOUNDATION PLAN REPRESENT THE MINIMUM REQUIREMENTS. IF WEATHER, TEMPERATURE OR PLACEMENT CONDITIONS INCREASE THE LIKELIHOOD OF SHRINKAGE CRACKS, INSTALL ADDITIONAL JOINTS AS REQUIRED BY ACI RECOMMENDATIONS.
5. PROVIDE 4" CONCRETE SLAB REINFORCED WITH 6x6-W1.4xW1.4 WELDED WIRE FABRIC ON 4" POROUS FILL AND 10 MIL VAPOR BARRIER.
6. PROVIDE (2)-#4 BARS x 36" LONG, 4" APART AT MID-DEPTH OF SLAB AT ALL RE-ENTRANT CORNERS AND AT SAW JOINT TERMINATIONS. ALL NOT SHOWN FOR CLARITY.
7. PROVIDE SLAB TURNDOWN EDGE SAME WIDTH OF WALL 8" DEEP. PROVIDE REINFORCING PER TYPICAL DETAIL.

FOOTING SCHEDULE			
MARK	SIZE	THICK	REINFORCING
(A)	2'-0" x CONT.	12"	(3)-#5 CONT. @ BOT.
(B)	3'-0" x 3'-0"	12"	(3)-#5 TOP AND BOT. EA. WAY

NOTE: IF THIS DRAWING IS A REDUCTION, GRAPHIC SCALE MUST BE USED.

GRAPHIC SCALE:




HUDSON+ASSOCIATES
ARCHITECTS
120 WEST QUEENS WAY SUITE 201
(757) 722-1964
HAMPTON, VA.
23669

□ □ □
BROGDEN LANE
ICF / MR HOME
FOR HNN CSB

□ □ □

□ □ □
SEPT. 3, 2008



□ □ □
FOUNDATION PLAN

JOB NUMBER 0704

S1.01